BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2023-24/OW/WORK_INDENT2523

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/KPPP/16/2023-24, Date: 02-02-2024

Name Of Work: Improvements to Roads and Drains at Raghuram Layout and Surrounding areas in New Ward No. 12 (Doddabommasandra).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. S S Enterprises, Prop. Nagaraj M	
				In Figures	In Words
1	111.13	Earth work Excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. (PWD SR 2023-24 Vol -I Pg No 5 item no 1.4.1)	Cum	175.00	Rupees One Hundred Seventy Five Only
2	26.46	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. . Mix 1:4:8 Using 40 mm nominal size graded crushed coarse aggregates (PWD SR 2023-24 Vol -I Pg 15 item no 2.1.2)	Cum	4599.00	Rupees Four Thousand Five Hundred Ninety Nine Only
3	2.91	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification H. All other type of structures (PWD SR 2023-24 Vol -I Pg 99 item no 2.11.h)	Tonne	76999.00	Rupees Seventy Six Thousand Nine Hundred Ninety Nine Only
4	48.51	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates (PWD SR 2023-24 Vol -I Pg 16 item no 2.4.2))	Cum	6499.00	Rupees Six Thousand Four Hundred Ninety Nine Only
5	176.40	Providing and laying 100mm thick pre-cast cover slabs over Road side drains / utility ducts / Rain water harvesting pit of width not exceeding 1000 mm using M20 concrete reinforced with TMT bars Fe 550 @ 6kg/ m2, slabs jointed in CM 1:3 proportion and nicely finished Including providing holes in the Cover slabs wherever necessary for easy drainage of surface water including of labour, materials, scaffolding, usage of machinery, curing, lead and lift charges etc, Complete. (PWD SR 2023-24 Vol -II Pg No. 177 item No. 17.14)	Sqm	949.00	Rupees Nine Hundred Forty Nine Only
6	142.25	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 15 km = 150 t.km (PWD SR 2023-24 Vol-III Page No. 5, Item No.1.4A)	T.Km	139.00	Rupees One Hundred Thirty Nine Only

Signature of the Contractor

Executive Engineer,
Byrasandrapura Division
Bruhat Bengaluru Mahanagara Palike

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು